

**TABLE 2**

Comparison of PREE/CA Presumptive Remedy Application Criteria for Capping with Conditions at Site LF01  
*EE/CA for Site LF01, Bellows AFS*

<b>Condition or Parameter</b>	<b>Presumptive Remedy Profile Value</b>	<b>Does Site LF01 Match the Presumptive Remedy Profile Value?</b>	<b>Comments</b>
<b>Landfill</b>			
Type of Waste	Municipal or low-hazard military-specific waste	YES	Site LF01 contains primarily construction/demolition waste, municipal, and minor military waste.
Volume of Landfill Waste	> 100,000 cubic yards of waste	NO	Site LF01 contains approximately 13,000 cubic yards of waste; based on this, the PREE/CA guidance recommends that a more detailed analysis be conducted rather than using the presumptive remedy approach.

Source: U.S. Army Corps of Engineers. May 1997. *United States Air Force Presumptive Remedy Engineering Evaluation/Cost Analysis (PREE/CA)*, 2nd Edition. Contract No. DACA-45-93-D-0027.